

FIELD SERVICE BULLETIN NO. 6

5. Drill cylinder to match housing lock bolt holes, and install lock bolt.
6. Reinstall wheel and tire and install in gear.
7. Make an operational check to ascertain that all adjustments are functioning properly and clearances are adequate.

